



CITY OF ANN ARBOR
PROJECT MANAGEMENT SERVICES UNIT
100 NORTH FIFTH AVE. P.O. BOX 8647
ANN ARBOR, MICHIGAN 48107-8647
WWW.A2GOV.ORG
(734) 794-6410

For Immediate Release
April 17, 2009

Homayoon Pirooz, P.E., Manager
hpirooz@a2gov.org
734-794-6411

Notice of Temporary Traffic Control Plan
HURON PARKWAY-NIXON ROAD IMPROVEMENT PROJECT
Construction Stage 2 of 5 - April 22 to June 1, 2009

Location and Limits of Affected Area:

Nixon Road from the intersection of Plymouth Road to the intersection of Aurora Street. Huron Parkway from the intersection of Plymouth Road to the intersection of Traverwood Dr.

Description of Construction:

The Huron Parkway – Nixon Road Improvement project will be constructed in 5 Stages and will include the following:

Nixon Road: complete reconstruction of the street and addition of new storm sewer and water quality control storm sewer structures. The proposed work will also include on-street bike lanes on both sides, a new mid block crossing with a refuge island, two new bus poll-outs with shelters, a right turn lane to the Plymouth Road shopping center, new sidewalks, and new LED energy efficient street lights.

Huron Parkway: partial reconstruction of the street, transition from a five-lane traffic flow at the Plymouth Road intersection to a two-lane traffic flow at the Nixon Road intersection, and a new bike lane. The new on-street parking and the bus-stop on the south side will create the opportunity for the park-and-ride customers, who may currently have their cars towed away if parked all day the at the adjacent shopping centers parking lots.

Nixon Road-Huron Parkway Intersection: full reconstruction of the intersection will include the installation of a modern roundabout, refuge islands at all four pedestrian crossing points, lighted pedestrian crossing overhead signs, rumble strips at each approach to the intersection, ADA ramps and new sidewalk, and landscaping.

Temporary Construction Traffic Control Plan for Stage 2:

- The NB Nixon Road traffic at the Plymouth Rd. intersection will be directed east on Plymouth Rd., north-west on Huron Parkway., north on Service Dr., west on Aurora St. to Nixon Rd.
- The SB Nixon Road traffic at the Aurora intersection will be directed east on Aurora St., south on Service Dr., south-east on Huron Parkway to Plymouth Road.
- The EB Huron Parkway traffic at the Traver Wood intersection will be directed south on Traver Wood Dr., east on Plymouth Rd. to the intersection of Plymouth Rd. and Huron Parkway.
- The WB Huron Parkway traffic at the intersection of Plymouth Rd. will be directed west on Plymouth Rd., north on Traver Wood Dr., to the intersection of Traver Wood Dr. and Huron Parkway.

During this construction the traffic may experience brief delays within the areas influenced by this work. Detour signs will be posted for this construction; however the motorists are advised to seek alternate routes. To maintain the safety of all, please reduce speeds and drive cautiously through work zones. We thank you in advance for your patience as these necessary public infrastructure improvements are completed.

Project Contacts:

City of Ann Arbor

Igor V. Kotlyar, P.E., Senior Project Engineer, (734) 794-6410 x43634

David Clemons, Construction Supervision, (734) 323-7942

Orchard, Hiltz & McCliment, Inc.

Andrew A. Konyha, Civil Engineer, (734) 891-2448

Pamar Construction Company

Steve Brown, Construction Contractor, (586) 405-2391